

CARR-1450
John Dorsey Farm
Gaither (vicinity)

c. 1915

Summary:

This was the farm of John Dorsey at least as early as 1862, and the 1877 atlas notes it owned by a J. M. Dorsey. In 1917 it was the J. Dorsey Farm, of 320 acres, and in the 1960's it was still owned by a Jonathan Dorsey. The farm has been subdivided for housing, but the original buildings were retained on a large lot. According to the current owner, the barn was built about 1915. Judging from its construction, this is a reasonable estimate, and the house and hog peg must also date from the same period. The entire farm must have been rebuilt in a substantial building campaign of that time, perhaps as the result of some natural calamity. It is unusual to find a farm all of one period, even this late. The house is no longer a traditional Carroll County building, but shows the influence of national trends, being a blend of a four square with some colonial revival motifs. The barn, on the other hand, is still a traditional bank barn. Unfortunately, it is scheduled for demolition.

Maryland Historical Trust State Historic Sites Inventory Form

MARYLAND INVENTORY OF Magi No.
HISTORIC PROPERTIES DOE yes no

1. Name (indicate preferred name)

historic John Dorsey Farm

and/or common

2. Location

street & number 6271 Old Washington Road not for publication

city, town Sykesville vicinity of congressional district

state Maryland county Carroll

3. Classification

Category	Ownership	Status	Present Use
<u> </u> district	<u> </u> public	<u> </u> occupied	<u> </u> agriculture <u> </u> museum
<u> </u> building(s)	<u> </u> private	<u> </u> unoccupied	<u> </u> commercial <u> </u> park
<u> </u> structure	<u> </u> both	<u> </u> work in progress	<u> </u> educational <u> </u> private residence
<u> </u> site	Public Acquisition	Accessible	<u> </u> entertainment <u> </u> religious
<u> </u> object	<u> </u> in process	<u> </u> yes: restricted	<u> </u> government <u> </u> scientific
	<u> </u> being considered	<u> </u> yes: unrestricted	<u> </u> industrial <u> </u> transportation
	<u> </u> not applicable	<u> </u> no	<u> </u> military <u> </u> other:

4. Owner of Property (give names and mailing addresses of all owners)

name Anne Schuler

street & number 6271 Old Washington Road telephone no.: 795-1471

city, town Sykesville state and zip code MD 21784

5. Location of Legal Description

courthouse, registry of deeds, etc. Courthouse Annex liber

street & number 55 North Court Street folio

city, town Westminster state MD

6. Representation in Existing Historical Surveys

title

date federal state county local

pository for survey records

city, town state

7. Description

Survey No. CARR-1450

Condition		Check one	Check one	
<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input checked="" type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site	
<input checked="" type="checkbox"/> good	<input type="checkbox"/> ruins	<input type="checkbox"/> altered	<input type="checkbox"/> moved	date of move _____
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed			

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

Summary:

The John Dorsey Farm is located at 6271 Old Washington Road, on the east side of the road, approximately 4 miles southeast of Winfield and about 3¼ miles northwest of Sykesville. The farm complex sits well back from the road on a generally flat site and consists of a frame house, a frame bank barn, and a hog pen. The house is a 2½-story, three-bay by four-bay frame structure with a rubble stone foundation, German siding with corner pilasters, and a hip roof with diamond-pattern asphalt shingles and a widow's walk. On the northwest elevation, the first story has a central door with a four-light transom. There is a 1/1 sash on either side of the doorway. The first story has a one-story, three-bay porch, with Greek Doric columns. There is a dormer on the roof with two 1/1 sash. The house has a wood box cornice with a wide eave. About 200 feet northeast of the house is a bank barn with a forebay that faces southeast. The barn has five circular-sawn bents that are mortised and tenoned and pegged. Each bent has five posts. The bents have a Queen post truss supporting the roof. The barn is slated for demolition. About 25 feet northeast of the barn is a hog pen. It has a concrete foundation, vertical-board siding with some aluminum on the southeast, and a gable roof with a northeast to southwest ridge.

Contributing Resources: 3

The John Dorsey Farm is located at 6271 Old Washington Road, on the east side of the road, approximately 4 miles southeast of Winfield and about 3¼ miles northwest of Sykesville. The farm complex sits well back from the road on a generally flat site and consists of a frame house, a frame bank barn, and a hog pen.

The house is a 2½-story, three-bay by four-bay frame structure with a rubble stone foundation, German siding with corner pilasters, and a hip roof with diamond-pattern asphalt shingles and a widow's walk with a vertical-board balustrade at the peak. There are two interior brick chimneys inside the widow's walk. The German siding is unique in that it has an ovolo moulding, instead of the more traditional cavetto or bevel. The house faces northwest towards the road. On the northwest elevation, the first story has a central door with one large light, and sidelights with three lights over one panel. There is a four-light transom. There is a 1/1 sash on either side of the doorway. The first story has a one-story, three-bay porch set on brick piers, with Greek Doric columns and a half-hip roof. The second story has three 1/1 sash. There is a dormer on the roof with two 1/1 sash, wood shingles on the northwest elevation, and a hipped roof with a lightning rod. The house has a wood box cornice with a wide eave.

MARYLAND HISTORICAL TRUST
STATE HISTORIC SITES INVENTORY FORM

Survey No. CARR-1450

Description (continued)

Section 7 Page 2

The northeast elevation has two four-light casements in the foundation. The first story has four 1/1 sash set in two pairs, one in each end. The second story is identical to the first. There is a dormer on the roof identical to the northwest elevation. The southeast elevation has a one-story, three-bay porch, 2½ bays of which are enclosed. The porch has square boxed posts on brick piers and a half-hip roof. The east end of the porch has an original five-lying-panel door that leads to the house. The second story of the southeast elevation has three 1/1 sash and a five-lying-panel door set between the south and south-center bays. There is a railing along the top of the south end of the porch. The roof contains a typical dormer. The southwest elevation has a four-light casement in the west bay of the foundation. The south bay has hurricane doors. Just west of these is a low stone foundation with concrete on top and a four-light casement on the southwest. The first and second stories have four 1/1 sash, like on the northeast elevation, and the roof has a typical dormer.

About 200 feet northeast of the house is a bank barn with a forebay that faces southeast. The southeast elevation lower story has horizontal beaded-edge-and-center boards. The doors have beaded-edge-and-center vertical boards. They are dutch doors hung on machine-cut strap hinges, while the windows in this story have 6/6 sash. The lower story has, from south to east, a door, a window, a door, a window, two doors, a window, a door, a window, and a door. There is a stone wall on the east end underneath the forebay and a steel post at the south corner of the bay. The upper story has vertical-board siding. There are three vents to the south, then a vertical board door on rollers, two more vents, another door, and three vents to the east. The barn has a gable roof with diamond-pattern asphalt shingles and four lightning rods. The southwest elevation lower story has vertical-board siding, with an opening, a 6/6 sash, a typical dutch door, and another 6/6 sash. The upper story has three vents. The gable end vent has been closed up, but retains a pediment above the opening with dentils and a drop pendant. The northwest elevation lower story has an addition on the north side. The west side of the ramp has a stone wall. The west side of the barn has a 4/4 sash. Each sash is set on its side. The upper story also has an addition on the north side. The southwest elevation of this addition has a doorway. The barn has two pair of wagon doors on rollers in the center of the northwest elevation, then two vents with window openings in the bottom of them, to the west. The northeast elevation has two 4/4 sash set on their sides in the lower story. The upper story also has three vents. The gable end has two vents, and there is an opening in the peak with the same pediment as found on the southwest elevation.

The lower story of the barn has three summer beams with five posts under each and block capitals on top of the posts beneath the summer beam. The posts are mortised and tenoned and pegged into the blocks. The blocks have chamfered corners, and the summer beams have half-lap scarfs that are pegged. All of the timber is circular sawn. The joists

MARYLAND HISTORICAL TRUST
STATE HISTORIC SITES INVENTORY FORM

Survey No. CARR-1450

Description (continued)

Section 7 Page 3

run northwest to southeast from the northwest wall to the northwest summer beam, then from the northwest summer to the southeast summer, and finally, separately, from the southeast summer to the forebay. Several of the joists are only of two pieces, with a half-lap scarf and two pegs at the center summer beam. The southeast wall is frame, set on a low concrete foundation. The southwest wall is frame on a low stone foundation. The upper story has two center threshing floors and a hay mow on each end. There is a granary in the west corner. The barn has five circular-sawn bents that are mortised and tenoned and pegged. Each bent has five posts. The bents have a Queen post truss supporting the roof. The top girt connecting the Queen post truss has through-tenons with wedges. The center girt has metal straps fastening it to the posts, as well as pegged joints. The rafters are approximately 2 x 4's that are mitered at the ridge, and there is a hay track. The barn is slated for demolition.

About 25 feet northeast of the barn is a hog pen. It has a concrete foundation, vertical-board siding with some aluminum on the southeast, and a gable roof with a northeast to southwest ridge. It has inverted V-seam roofing. The southeast elevation has three low openings, and has concrete pens on the exterior. The southwest elevation has a vertical-board door on machine-cut strap hinges set to the west, and a small door set to the south. There is an opening in the gable end. The northwest elevation has no openings. The northeast elevation lower story is the same as the southwest elevation. There is no opening in the gable end. The hog pen has a circular-sawn, mortised-and-tenoned-and-pegged, heavy-timber, braced frame. There is an aisle along the northwest side with two pens on the southeast. This arrangement has been altered. There are stairs along the northeast end to the upper story. The rafters are 2 x 4's that are circular sawn and mitered at the ridge.

8. Significance

Survey No. CARR-1450

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400–1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500–1599	<input checked="" type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600–1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/
<input type="checkbox"/> 1700–1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian
<input type="checkbox"/> 1800–1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input checked="" type="checkbox"/> 1900–	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input type="checkbox"/> other (specify)

Specific dates c. 1915

Builder/Architect

check: Applicable Criteria: ☐ A ☐ B ☒ C ☐ D
and/or

Applicable Exception: ☐ A ☐ B ☐ C ☐ D ☐ E ☐ F ☐ G

Level of Significance: ☐ national ☐ state ☒ local

Prepare both a summary paragraph of significance and a general statement of history and support.

Geographic Organization: Piedmont

Chronological/Development Period: Industrial/Urban Dominance A.D. 1870-1930

Historic Period Themes: Agriculture, Architecture

Resource Types: Small family farm, Rural vernacular

This was the farm of John Dorsey at least as early as 1862, and the 1877 atlas notes it owned by a J. M. Dorsey. In 1917 it was the J. Dorsey Farm, of 320 acres, and in the 1960's it was still owned by a Jonathan Dorsey. The farm has been subdivided for housing, but the original buildings were retained on a large lot. According to the current owner, the barn was built about 1915. Judging from its construction, this is a reasonable estimate, and the house and hog peg must also date from the same period. The entire farm must have been rebuilt in a substantial building campaign of that time, perhaps as the result of some natural calamity. It is unusual to find a farm all of one period, even this late. The house is no longer a traditional Carroll County building, but shows the influence of national trends, being a blend of a four square with some colonial revival motifs. The barn, on the other hand, is still a traditional bank barn. Unfortunately, it is scheduled for demolition.

9. Major Bibliographical References

Survey No. CARR-1450

1862, 1877, 1917 maps

10. Geographical Data

Acreage of nominated property c. 1915Quadrangle name WinfieldQuadrangle scale 1:24000

UTM References do NOT complete UTM references

A	Zone	Easting	Northing

B	Zone	Easting	Northing

C	Zone	Easting	Northing

D	Zone	Easting	Northing

E	Zone	Easting	Northing

F	Zone	Easting	Northing

G	Zone	Easting	Northing

H	Zone	Easting	Northing

Verbal boundary description and justification

List all states and counties for properties overlapping state or county boundaries

state	code	county	code
-------	------	--------	------

state	code	county	code
-------	------	--------	------

11. Form Prepared By


name/title Kenneth M. Short, Historic Plannerorganization Carroll County Planningdate January 18, 1996street & number 225 North Center Streettelephone (410) 857-2145city or town Westminsterstate MD

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
Shaw House
21 State Circle
Annapolis, Maryland 21401
(301) 269-2438

MARYLAND HISTORICAL TRUST
DHCP/DHCD
100 COMMUNITY PLACE
CROWNSVILLE, MD 21032-2023
514-7600




FREEDOM

DISTRICT N°5

Scale 1 1/2 Inches to the Inch
Morgans

LOUISVILLE P.O.



FREEDOM BUSINESS

John Duckebaugh, Manufacture and Collars. Shop on west of Freedom Post office. Wm. M. Hines, Physician and druggist, one mile west of. Capt. Thomas Payot, Cook and Practical Miner. J. Wadlow & Son, Dealers in Boots, Shoes, Hardware, Paints, Oils, Dye.


CARR-1450

John Dorsey Farm

6271 Old Washington Road

Lake, Griffin & Stevenson Atlas, 1877


GARROLL Co. MD.



EXPERIMENTAL MATERIALS

Daniel

CARR-1450
John Dorsey Farm
6271 Old Washington Road
Rand McNally Map, 1917



MILE


ROAD

HARD-SURFACE ALL WEATH

Heavy-duty - _____ + 1.4

Medium-duty _____ + LA

Loose surface, graded,

 U. S. Route

QUADRANGLE LOCATION

CARR-1450

John Dorsey Farm

6271 Old Washington Road

Winfield quad

WINFIELD, MD.

NE/4 MOUNT AIRY 15' QUADRANGLE
N3922.5-W7700/7.5

N3922.5—W7700/7.5

EDITION OF 1950

PHOTOREVISED 1979

AMS 5562 I NE-SERIES V833

74

Boundary lines shown in purple compiled from latest information available from the controlling authority



John Dorsey Farm
6271 Old Washington Rd.
Carroll County, Maryland
Photo: Kenneth M. Short
Date: June 1995
Neg. Loc.: Maryland Historical Trust
house - NE & NW elevs
1/4



CARE-1450

John Dorsey Farm
6271 Old Washington Rd.
Carroll County, Maryland

Photo: Matt Hankins

Date: January 1995

Neg. loc.: Maryland Historical Trust
barn - SW & SE elevs.

2/4

2011 JAN 22 17 36



John Dorsey Farm
6271 Old Washington Rd.
Carroll County, Maryland
Photo: Matt Hankins
Date: January 1995
Neg. Loc.: Maryland Historical Trust
barn-NE & NW elevs.
3/4



John Dorsey Farm

6271 Old Washington Rd.

Carroll County, Maryland

Photo: Matt Hankins

Date: June 1995

Neg. loc.: Maryland Historical Trust
barn - upper story bent

4/4